



**NOTES:**

1. REFER TO GI-1 NOTES FOR GUIDELINES AND CHECKLIST.
2. ALL MATERIAL AND WORKMANSHIP FOR CURB CUTS SHALL CONFORM TO CITY OF DUBLIN STANDARDS.
3. CURB CUT INLETS SHALL BE ADEQUATELY SIZED, SPACED, AND SLOPED TO MEET HYDRAULIC REQUIREMENTS. SEE NOTE 2, DETAIL GI-6A FOR REFERENCE.
4. BOND NEW CURB AND GUTTER TO EXISTING CURB AND GUTTER WITH EPOXY AND DOWEL CONNECTION.



**BIORETENTION COMPONENTS: CURB CUT AT BULBOUT INLET DETAIL**

<b>GREEN INFRASTRUCTURE TYPICAL DETAILS</b> CITY OF DUBLIN PUBLIC WORKS	SCALE: NOT TO SCALE	APPROVED:  _____ PUBLIC WORKS DIRECTOR
	DATE: MAY 11, 2018	
	DRAWN BY: K. K.	
	CHECKED BY: A. R.	

GI-6C